

MS4 PROGRAM

CONTROL OF SITE CONSTRUCTION WASTE

- **PROPERLY DISPOSE OF ALL DISCARDED BUILDING MATERIALS, OFF-SITE**
- **REMOVE FROM THE SITE ALL CONCRETE TRUCK WASH-OUTS**
- **REMOVE FROM THE SITE ALL CHEMICALS**
- **REMOVE FROM THE SITE ALL TRASH AND LITTER**
- **REMOVE FROM THE SITE ALL SANITARY WASTES**
- **REMOVE AND SWEEP CLEAN ALL SEDIMENT TRACKED ONTO STREET PAVEMENTS**

Construction crews and site operators shall be responsible for ongoing monitoring of conditions and routine control of site construction waste. Trash and litter shall be removed prior to being subject to wind blown conditions. Street pavements shall be cleaned within 4 hours or sooner of an occurrence of uncontrolled site construction materials. Proper off-site disposal shall be at sufficient intervals to prevent pollution of stormwater runoff.